

Importance of Fixing Leaks

Even small leaks add up to a lot of water over time. The chart at right shows how much water flows through a leak the size of the circle indicated. A pinprick sized hole means 3,600 gallons a month or 43,200 gallons a year. When this water flows through your meter, you are paying for water you are not using and the District is paying to pump this water - extra wear on the pumps and the cost of electricity to run the pump. Help preserve your water system and repair leaks on your service lines. We monitor the distribution system for leaks by visual inspection. Once the system is fully metered, we will be able to check the distribution system leakage on a monthly basis to determine if we have system leaks.



Water Loss in Gallons

Leak this Size	Loss Per Day	Loss Per Month	Leak the Size	Loss Per Day	Loss Per Month
.	120	3,600	●	6,640	199,520
•	300	10,800	●	6,964	209,520
•	693	20,790	●	8,424	252,720
•	1,200	36,000	●	9,585	296,640
•	1,920	57,600	●	11,324	339,720
•	3,095	92,880	●	12,750	361,600
•	4,295	128,880	●	14,952	448,560

How to Check Your Meter For Leaks

1. Locate your water meter. It is usually found in a small concrete or plastic box near the street.

2. If you need help locating your water meter, contact the P.U.D.

3. Turn off all water at the house and in the yard, including water-using appliances in the home.

4. Remember to shut off all indoor and outdoor faucets.
5. Check and record the current meter reading.

6. Wait at least 15 minutes before checking your meter again.

7. Remember, DO NOT use any water while you are waiting!

8. Read the water meter again. If the reading has changed, then you may have a leak that may require immediate attention.

Water Use Efficiency

Water use efficiency is a “proactive approach” to protect public health and water supplies. Droughts, climate change, growth demands and fewer granted water rights may lead to future long-term water disruptions due to declining water supplies. The District water use efficiency (WUE) program effectively plans and implements measures that can result in fewer water emergencies:

- Contributes to long-term water supply reliability and public health protection.
- Promotes good stewardship of the state’s water resources.
- Ensures efficient operation and management of our water systems.

New WUE goals were approved in September 2018. To view all 6 Groups of WUE Goals please visit the districts website. <https://mason-pud1.org/water-use-efficiency/> Under **Water Use Efficiency** click on Current Water Use Efficiency Goals.

The 2021 DSL for the Lake Arrowhead Water System is

Total Water Produced (TP) - 6,343,000 gallons
Authorized Consumption (AC) – 3,383,636 gallons
DSL Volume – 2,959,364 gallons

Note: Gallons for the entire system.

DSL Percentage – 46.7%
3-Year Rolling Average DSL – 51.6%

The approved 2018 goals for Group 5 40% - 50% DSL are:

Production:

- Reduce DSL to 25% in 6 years.
- Reduce DSL to 15% in 12 years.
- Reduce total annual water production by 1% in 6 years.
- Reduce peak month production by 1% per ERU in 6 years.

Consumption:

- Reduce peak daily demand by 2% per ERU in 6 years.
- Reduce peak month ADD by 2% in 6 years.

Progress of Meeting Goals:

Production:


- Reduced DSL by 49% in the last 6 years.
- Reduced DSL by 41% in the last 12 years.
- Reduced total annual water production by 33% per ERU in the last 6 years.
- Reduced peak month production by 25% per ERU in the last 6 years.

Consumption:

- Reduced peak daily demand by 39% per ERU in 6 years.
- Reduced peak month ADD by 11% in 6 years.

Steps to Meet Goals:

- Continue leak detection and repair leaks when found
- Repaired leaks in February, March, and May
- Replaced 2,500 linear feet of mainline
- Distribution system water audit implemented



Booster Station and Generator

Water Use Efficiency Definitions

Authorized Consumption (AC): volume of water used by consumers as shown through meter readings, fire-fighting, system flushing, tank cleaning and street cleaning.

Average Daily Demand (ADD): average volume of water a typical single family home uses each day.

Distribution System Leakage (DSL): water lost from the system through leaking pipes, illegal water use,

malfunctioning meters or meter reading errors. The volume difference of total water produced and authorized consumption (TP-AC).

Percent DSL= [(TP-AC)/TP]x100%

Total Water Produced (TP): volume of water pumped from a well, diverted from a surface water or purchased from another system.

Water Use Efficiency (WUE) Goal: a set target for water usage approved by the Board of Commissioners through the public process.

Water Use Efficiency Measure: actions set by the Board of Commissioners to reduce water loss and water demand approved through the public process.



Lake Arrowhead Water System

2022 Annual Water Quality & Water Use Efficiency Report

PWSID #436003

System Summary

Welcome to the 2022 Water Quality and Use Efficiency Report. This report is designed to inform you about the water and services the district delivers to you every day. Our goal is to provide you with a safe and dependable supply of drinking water. To comply with State and Federal water quality laws, 12 water quality tests were performed for your system in 2022.

Our water source is the Lake Arrowhead Well 3 which draws water from an aquifer 73’ deep located off Star Lake Road. The booster station and reservoir are located at the well site. The 105,000 gallon concrete reservoir was cleaned and inspected in 2019. The system is continuously chlorinated. All water services and source are metered. There are 258 connections and the system is approved for 400 connections.

We received funding through the Department of Health Drinking Water State Revolving Fund to complete the rest of the mainline replacement.

Design for the mainline replacement is underway. There is no completion date for this.

PROJECT UPDATES - 2,500’ of 6” HDPE was installed along Quillayute Trail, Colville Trail, Skokomish Trail, Tulalip Trail, and Quinault Trail and fire hydrants were installed at the end of each road. Iron and Manganese Remove Treatment went out to bid and was awarded to the lowest bidder, General Mechanical Inc, for \$225,629.00. This is another State Revolving Fund Project and this was 100% loan forgiveness. All improves will not impact your current rates.

A Water System Plan is available from our office that provides more information about the Lake

Arrowhead Water System— such as potential sources of contamination. We are currently working on updating the water system plan, the plan was last updated in 2000. Our well has been rated by the Washington State Department of Health as high for risk or susceptibility to contamination. More information regarding this rating can be obtained by contacting PUD No. 1.

The State Dept. of Health has Source Water Assessment Program (SWAP) data available online at: <https://fortress.wa.gov/doh/swap/> which lists potential contamination for each Group A water source in the state. This is an interactive Map.

If you have any questions regarding this report, the water or PUD No. 1 please contact Brandy Milroy, Water Resource Manager at 360-877-5249 or brandym@mason-pud1.org. Also, don’t forget PUD 1 board meetings are the 2nd and 4th Tuesdays of each month at our office in Potlatch (1 mile south of Hoodsport, WA) at 1 pm. The public is welcome to our meetings.

the rest of the whole system mainline to be replaced

Health Effects of Contaminates

Nitrates: As a precaution we always notify physicians and health care providers in the area if there is ever a higher than normal level of nitrates in the water supply. Infants below the age of six months who drink water containing nitrate in excess of the MCL could become seriously ill and, if untreated, may die. Symptoms include shortness of breath and “blue baby” syndrome. Nitrate levels may rise quickly for short periods of time because of rain fall or agricultural activity. If you are caring for an infant, you should ask for advice from your health care provider.

Total Coliform: Coliforms are bacteria that are naturally present in the environment and are used as an indicator that other, potentially harmful, bacteria may be present.

Arsenic: YYour drinking water currently meets EPA’s standard for arsenic. EPA continues to research the health effects of low levels of arsenic, which is a mineral known to cause cancer in humans at high

concentrations and is linked to other health effects such as skin damage and circulatory problems.

Copper: Copper is an essential nutrient, but some people who drink water containing copper in excess of the action level over a relatively short amount of time could experience gastrointestinal distress. Some people who drink water containing copper in excess of the action level over many years could suffer liver or kidney damage. People with Wilson’s Disease should consult their personal doctor.

Lead: Infants and children who drink water containing lead in excess of the action level could experience delays in their physical or mental development. Children could show slight deficits in attention span and learning abilities. Adults who drink water with excess lead over many years could develop kidney problems or high blood pressure.

Manganese: Manganese is known to occur naturally in well water due to the type of rock a well may

be drilled into. Concentrations above the national guidelines may contribute to problems with taste, odor and color of the water coming out of your tap.

Chloride, Sodium and Salt Water Intrusion: Chloride and sodium levels rise when a well begins to pump from an aquifer mixing with sea water.

Turbidity: Turbidity has no health effects. However, turbidity can interfere with disinfection and provide a medium for microbial growth. Turbidity may indicate the presence of disease-causing organisms. These organisms include bacteria, viruses and parasites that can cause symptoms such as nausea, cramps, diarrhea and associated headaches.



Reason for Reporting Contaminants

The contaminant results table provided lists the drinking water contaminants we detected that are applicable for the calendar year of this report. The presence of contaminants in the water does not necessarily indicate that the water poses a health risk. Unless otherwise noted, the data presented in the table is from testing done in the calendar year of the report. The EPA or the state requires us to monitor for certain contaminants less than once per year because the concentrations of these contaminants do not change.

Water Quality Summary - Lake Arrowhead Water System PWSID #436003

Contaminant	Violation Yes/No	Level Detected (range)	Unit Measurement	MCLG	MCL	Typical Source
Microbiological Contaminants						
Total Coliform Bacteria	NO	0	Present or Absent	0	One Positive monthly sample	Naturally present in the environment
Fecal Coliform and E.coli	NO	ND	Present or Absent	0	One Positive monthly sample	Human and animal fecal waste
Inorganic Contaminants						
Nitrate (as Nitrogen) (03/02/2022) Well #3	NO	ND	mg/L	10.0	10	Runoff from fertilizer use; leaching from septic tanks, erosion of natural deposits
Copper (06/29/2022) Distribution Samples (5)	NO	Max 0.037 (<.003-0.037) 90th %: <0.028	mg/L	1.3	AL=1.3	Corrosion of household plumbing systems; Erosion of natural deposits
Lead (06/29/2022) Distribution Samples (5)	NO	Max 0.0042 (<0.001-0.0042) 90th %: <0.001	mg/L	0	AL=0.015	Corrosion of household plumbing systems; Erosion of natural deposits
Secondary Contaminants						
Iron (03/05/2021) Well #3	NO	0.23	ppb	300	300	Secondary contaminant that causes discoloration and taste; naturally present
Manganese (06/28/2019) Well #3	NO	0.08	ppb	50	50	Secondary contaminant that causes discoloration and bad taste; naturally present
Chloride (05/08/2015) Well #3	NO	4.00	ppm	250	250	Secondary contaminant; salt water intrusion
Sulfate (05/08/2015) Well #3	NO	<1	ppm	250	250	Secondary contaminant that causes discoloration and bad taste; naturally present
Sodium (05/08/2015) Well #3	NO	6.57	ppm	N/A	SRL = 5	Secondary contaminant; bad taste
Disinfection Byproducts Stage 1 - System wide Running Annual Average						
Contaminant	MCL	Level Detected (range)	Unit Measurement	Range	Violation	Typical Source
Total Trihalomethanes (TTHM) (10/28/2020)	80	27.6	ppb	N/A*	NO	Byproduce of drinking water disinfection
Haloacetic Acids (HAA) (10/28/2020)	60	11.7	ppb	N/A*	NO	Byproduce of drinking water disinfection

*Samples taken only once every 3 years so there is no range during the year

What You Should Know About Water Quality

Drinking water, including bottled water, may reasonably be expected to contain at least small amounts of some contaminants. The presence of contaminants does not necessarily indicate that the water poses a health risk. More information about contaminants and potential health effects can be obtained by calling the EPA's Safe Drinking Water Hotline (1-800-426-4791).
Some people may be more vulnerable to contaminants in drinking water than the general population. Immuno-compromised persons such as persons with cancer undergoing chemotherapy, persons who have undergone organ transplants, people with HIV/AIDS or other immune system disorders, some elderly, and infants can be particularly at risk from infections. These people should seek advice about drinking water from their health care providers. EPA/CDC guidelines on appropriate means

to lessen the risk of infection by Cryptosporidium and other microbial contaminants are available from the Safe Drinking Water Hotline (1-800-426-4791).
Maximum Contaminant Levels (MCLs) are set at very stringent levels. To understand the possible health effects described for many regulated contaminants, a person would have to drink 2 liters of water every day at the MCL for a **lifetime** to have a **one-in-a-million** chance of having the described health effect.
The sources of drinking water (both tap and bottled) include rivers, lakes, streams, ponds, reservoirs, springs and wells. As water travels over the surface of the land or through the ground, it dissolves naturally occurring minerals, in some cases, radioactive material, and can pick up substances resulting from the presence of animals or human activity.

In the water quality table you will find many terms and abbreviations you might not be familiar with. To help you better understand these terms, we have provided the following definitions:

Action Level (AL) - The concentration of a contaminant which, if exceeded, triggers treatment or other requirements which a water system must follow.

Lead and Copper 90th Percentile - out of every 10 homes sampled, 9 were at or below this level.

Maximum Contaminant Level (MCL) - the highest level of a contaminant that is allowed in drinking water. MCLs are set as close to the MCLGs as feasible using the best available treatment technology.

Maximum Contaminant Level Goal (MCLG) - the level of a contaminant in drinking water below which there is no known or expected risk to health. MCLGs allow for a margin of safety.

Maximum Residual Disinfectant Level (MRDL) - the highest level of a disinfectant allowed in drinking water. There is convincing evidence that addition of a disinfectant is necessary for control of microbial contaminants.

Maximum Residual Disinfectant Level Goal (MRDLG) - the level of a drinking water disinfectant below which there is no known or expected risk to health. MRDLGs do not reflect the benefits of the use of disinfectants to control microbial contaminants.

N/A - not applicable.

Nephelometric Turbidity Unit (NTU) - a measure of the clarity of water. Turbidity in excess of 5 NTU is just noticeable to the average person.

Non-Detects (ND) - Laboratory analysis indicates that the contaminant is not present or not detected.

Parts per Billion (ppb) or micrograms per Liter (µg/l) - one part per billion.

Parts per Million (ppm) or Milligrams per Liter (mg/l) - one part per million corresponds to one minute in two years or a single penny in \$10,000.

Secondary Maximum Contaminant Level (SMCL) - these standards are developed to protect the aesthetic qualities of drinking water and are not health based.

State Reporting Level (SRL) - the level of contamination in which laboratory must report to the state.

Treatment Technique (TT) - a required process intended to reduce the level of a contaminant in drinking water.
< - Means 'less than'



Reservoir and Booster Station

State Waivers

Waivers mean no testing or modified testing frequency for a specified contaminant is required for a set period of time. The Washington State Department of Health reduced the monitoring requirements for SOC (pesticides) and Soil Fumigants because the source is not at risk of contamination. The last sample collected for these contaminants was taken on 04/26/2012 and was found to meet all applicable standards.

- Inorganic Contaminants:** 1 sample every 9 years;
- Synthetic Organic Contaminants** (herbicides): 1 sample every 9 years;
- Volatile Organic Contaminants:** 1 sample every 6 years;
- Dioxin, Diquat, Endothal, Glyphosphate, Insecticides:** complete waivers;
- Asbestos:** 1 sample every 9 years.

Unregulated Contaminants Statement

Unregulated contaminants are those for which EPA has not established drinking water standards. The purpose of unregulated contaminant monitoring is to help EPA determine their occurrence in drinking water and potential need for future regulation.

Secondary Contaminants Statement

Secondary contaminant standards are developed to protect the aesthetic (taste, color and odor) qualities of drinking water and are not health based. Secondary contaminants include iron, manganese, silver, chloride, sulfate and zinc. Exceeding the MCL for any of these secondary contaminants does not mean the water system is in violation of the state or federal standard.

Washington State Office of Drinking Water Lead Statement

In Washington State, lead in drinking water comes primarily from materials and components used in household plumbing and service lines. Mason PUD No. 1 is responsible for providing high quality water, but cannot control the variety of materials used in plumbing components. Elevated levels of lead can cause serious health problems, especially in pregnant women and young children.
To help reduce potential exposure to lead: for any drinking water tap that has not been used for 6 hours or more, flush water for thirty (30) seconds to two (2) minutes through the tap until the water is noticeably colder before using for drinking or cooking. You can use the flushed water for watering plants, washing dishes or general cleaning. Only use water from the cold-water tap for drinking, cooking, and especially for making baby formula. Hot water is likely to contain higher levels of lead. If you are concerned about lead in your water, you may wish to have your water tested. Information on lead in drinking water is available from EPA's Safe Drinking Water Hotline at 1-800-426-4791 or online at <http://www.epa.gov/safewater/lead>.
Tap Water and Bottled Water Safety
To ensure that tap water is safe to drink, the Washington State Board of Health and/or EPA



prescribe regulations that limit the amount of certain contaminants in water provided by public water systems. The Food and Drug Administration (FDA) and the Washington Department of Agriculture regulations establish limits for contaminants in bottled water that must provide the same protection for public health.

How to Clear Chlorine from Tap Water

Occasionally we are required to chlorinate the distribution system. When that occurs and you prefer not to drink chlorinated water, fill a pitcher with tap water and leave it either on the counter or in the fridge over night. The chlorine will dissipate and you should not taste it in your drinking water from the pitcher. A filter on your faucet or in a pitcher may, also, be used to remove chlorine.

Contaminants That May Be Present In Source Water

- Microbial contaminants**, such as viruses, parasites and bacteria, that may come from sewage treatment plants, septic systems, agricultural livestock operations and wildlife.
- Inorganic contaminants**, such as salts and metals, which can be occur naturally or result from urban storm water runoff, industrial or domestic wastewater discharges, oil and gas production, mining or farming.
- Pesticides and herbicides**, which may come from a variety · of sources, such as agriculture, urban storm water runoff and residential uses.
- Radioactive contaminants** which can occur naturally or result from oil and gas production and mining activities.
- Organic chemical contaminants**, including synthetic and volatile chemicals, which are by-products of industrial processes and petroleum production. They can also come from gas stations, urban storm water runoff and septic systems.