



ADDENDUM 2

Project: Jorstad Feeders Civil Construction

Date: 5/22/2026

To: Prospective Bidders

From: Jeremiah Waugh, PE-Engineering Manager for PUD1

Cc: Kristin Masteller-General Manager for PUD1; Emily Novotny, PE, Engineer-Toth; Benjamin Robsciotti, EIT, Designer-Toth; Justin Gardner, PE- DNR Engineer

ADDENDUM

Bidder shall sign and attach a copy of this Addendum with Bid Proposal.

Changes and clarifications to the Bid Documents and Plan-Set for the above-referenced project are as follows:

Q: Will the (6) 3-inch conduits need to be stacked, or may they lie side by side?

A: The (6) 3" conduit may be in any configuration, stacked or side by side.

Q: Can a circuit map of the existing wire layout be provided?

A: No. Call for locates to determine locations for all utilities. There will only be existing PUD power utilities near vaults 23A/B, 25A/B, 27A/B & 29A/B

Q: With the pond found between vaults 3-4 & 5-6, what is the suggested pathway for trench routing?

A: There is no alternative route. No standing water or saturation was observed during the walk through.

Q: Many staked vault locations have stormwater/creek conflicts, may we plan to install additional alternative drain pipe around these vaults to assist with the flow of said water away from the vault?

A: Yes, you may plan to install additional drain pipes around the vaults to assist with water flow. DNR minimum culvert is 18". Please account for this in your bid. Additionally, vaults may be shifted with engineering approval. Any change order associated with these drain pipes must be reviewed for approval by an engineer prior to installation.

Q: Can a few of the small trees in-line with vault locations be removed as needed for install?

A: We prefer shifting vaults before removing trees. Especially on DNR property.

Q: If the existing power is direct bury, what size is this conductor? There is no existing line for Mason PUD in this area. The existing UG power between vaults 23A/B & 25A/B is #2URD in 2" conduit. The UG power between vaults 25A/B & 29A/B may be #2URD direct buried. Call for locates to determine locations for all utilities.

Acknowledgement of receipt of Addendum: _____

SIGNATURE OF BIDDER