



ADDENDUM 1

Project: Lilliwaup Corner Rebuild

Date: 06/10/2026

To: Prospective Bidders

From: Jeremiah Waugh, PE-Engineering Manager for PUD1

Cc: Kristin Masteller-General Manager for PUD1

ADDENDUM

Bidder shall sign and attach a copy of this Addendum with Bid Proposal.

Changes and clarifications to the Bid Documents and Plan-Set for the above-referenced project are as follows:

1. PUD Furnished materials
 - a. Stick Conduit (except for riser sch 80)
 - b. Vaults
 - c. Cabinets (comes with 4-ways)
 - d. Padmount transformers
 - e. Poles
 - f. 500MCM 200 mil – EPR jacketed (3) 2500' rolls
 - i. 500 MCM URD ALUMINUM OKONITE OKOGUARD URO-J,080 OKOLENE W/3 RED STRIPES
 - g. #2 URD 200 mil -EPR Jacketed
2. Contractor Provided
 - a. Everything else
 - b. May use 8" helix instead of 10" as long as holding capacities are met
 - c. Assume Triple helix for swampy areas
3. Changes -
 - a. Remove V3 *to allow for a bore pit to cross the bay to be constructed next year*
 - b. P10 - Remove 4/0 riser becomes 500MCM Riser (UC3.3)
 - c. V1 Location Change – move to Sta 58+50 along Hwy 101
 - d. C1 Location Change – Along Robinson Rd
 - e. Construction Unit UC3.3GOS modified: Item 16 336 to 4/0 ASCR connector
4. Critical that minimum depths are obtained
 - a. WSDOT Stationing has been field marked with nails and paint
 - b. Contractor must redline drawing D1 with depths and offsets
 - i. Electronic reports are also acceptable, but must ensure the Stationing offsets are identified
5. Trench Minimum 1.5' wide
 - a. May use native backfill unless material is too large or angular –
 - i. Assume import cost to be worst case for entirety of trenched areas
 - b. Spoils disposed of spoils at an approved site. Not at the PUD 1 yard. There are some local

- options.
6. Vaults shall be:
 - a. Grouted
 - b. Swept out/cleaned
 7. Conduit ingress/egress through vaults to be staggered
 8. PUD will inspect vault installations and trenches.
 9. Contractor responsible for loading vaults and conduit from PUD yard
 - a. Contractor may load and bring material to site as needed
 - b. Once material leaves the PUD yard the contractor is responsible for material
 10. Lay down yard
 - a. Access to PUD1 Yard 6am to 4:30pm (Monday – Thursday)
 - i. If Friday access is needed PUD will provide a code for gate access to PUD Yard
 11. Mobilization not to exceed 10% of construction total
 12. Cutoff for addenda q's will be Monday June 22nd 3:00pm
 - a. I will send the final addendum, if there is any, before the end of day Thursday June 25th
 13. All addenda must be signed and included with the bid.
 14. See attached & on web, updated plan drawings
 15. See attached & on web, UC3.3 (500 MCM riser at P10)
 16. See attached & on web, UC3.3GOS (Modified item #16 only)
 17. See attached & on web, updated staking sheets
 18. See attached & on web, updated bid sheet
 - a. Assume hill holder construction/material costs w/ vaults on bid sheet
 19. Use updated bid sheet to submit bids.

Acknowledgement of receipt of Addendum: _____

SIGNATURE OF BIDDER